


N85-10104


DEVELOPMENT OF NEW AND IMPROVED POLYMER  
MATRIX RESIN SYSTEMS, PHASE 1

Ames Research Center  
Moffett Field, CA



DEC 83

DEPARTMENT OF DEFENSE  
PLASTICS TECHNICAL EVALUATION CENTER  
ARRADCQM, DOVER, N. J. 07801



19951214 017

U.S. DEPARTMENT OF COMMERCE  
National Technical Information Service

**NTIS**

1981/27

# DISCLAIMER NOTICE



**THIS DOCUMENT IS BEST  
QUALITY AVAILABLE. THE  
COPY FURNISHED TO DTIC  
CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO  
NOT REPRODUCE LEGIBLY.**

# DISCLAIMER NOTICE



**THIS DOCUMENT IS BEST QUALITY AVAILABLE. THE COPY FURNISHED TO DTIC CONTAINED A SIGNIFICANT NUMBER OF PAGES WHICH DO NOT REPRODUCE LEGIBLY.**

\*MSG DI4 DROLS PROCESSING-LAST INPUT IGNORED

\*MSG DI4 DROLS PROCESSING - LAST INPUT IGNORED

-- 1 OF 1

\*\*\*DTIC DOES NOT HAVE THIS ITEM\*\*\*

-- 1 - AD NUMBER: D439483  
-- 5 - CORPORATE AUTHOR: NATIONAL AERONAUTICS AND SPACE ADMINISTRATION  
-- MOFFETT FIELD CA AMES RESEARCH CENTER  
-- 6 - UNCLASSIFIED TITLE: DEVELOPMENT OF NEW AND IMPROVED POLYMER  
-- MATRIX RESIN SYSTEMS, PHASE 1,  
--10 - PERSONAL AUTHORS: HSU, M. S. ;  
--11 - REPORT DATE: DEC , 1983  
--12 - PAGINATION: 72P  
--15 - CONTRACT NUMBER: NAS2-11529  
--18 - MONITOR ACRONYM: NASA  
--19 - MONITOR SERIES: CR-166595  
--20 - REPORT CLASSIFICATION: UNCLASSIFIED  
--21 - SUPPLEMENTARY NOTE: PREPARED IN COOPERATION WITH HC CHEM  
-- RESEARCH & SERVICE, CORP., SAN JOSE, CA.  
--22 - LIMITATIONS (ALPHA): APPROVED FOR PUBLIC RELEASE; DISTRIBUTION  
-- UNLIMITED. ~~AVAILABILITY: NATIONAL TECHNICAL INFORMATION SERVICE,~~  
-- ~~SPRINGFIELD, VA 22161. NOS 10167.~~  
--33 - LIMITATION CODES: 1

---\*\*\*\*\*

END OF DISPLAY LIST  
<<ENTER NEXT COMMAND>>

NASA CONTRACTOR REPORT 166595

(NASA-CR-166595) DEVELOPMENT OF NEW AND  
IMPROVED POLYMER MATRIX RESIN SYSTEMS, PHASE  
1 (HC Chem Research and Service) 72 p  
HC A04/MF A01

N85-10104

CSCL 11B

G3/23 Unclas  
23267

Development of New and Improved Polymer Matrix  
Resin Systems (Phase I)

M. S. Hsu

CONTRACT NAS2-11529

December 1983

**NASA**

REPRODUCED BY  
NATIONAL TECHNICAL  
INFORMATION SERVICE  
U.S. DEPARTMENT OF COMMERCE  
SPRINGFIELD, VA. 22161

|  |  |  |  |  |  |
|--|--|--|--|--|--|
| 1. Report No.<br>CR 166595   |  | 2. Government Accession No.                          |  | 3. Recipient's Catalog No.                                 |  |
| 4. Title and Subtitle<br>DEVELOPMENT OF NEW AND IMPROVED POLYMER MATRIX RESIN SYSTEMS (PHASE I)  |  |  |  | 5. Report Date<br>December 1983                            |  |
|  |  |  |  | 6. Performing Organization Code<br>SC                      |  |
| 7. Author(s)<br>M. S. Hsu  |  |  |  | 8. Performing Organization Report No.                      |  |
| 9. Performing Organization Name and Address<br>HC Chem Research & Service, Corp.<br>3675 Skyview Dr.<br>San Jose, CA 95132   |  |  |  | 10. Work Unit No.<br>T4240                                 |  |
|  |  |  |  | 11. Contract or Grant No.<br>NAS2-11529                    |  |
| 12. Sponsoring Agency Name and Address<br>National Aeronautics and Space Administration<br>Ames Research Center<br>Moffett Field, CA 94035   |  |  |  | 13. Type of Report and Period Covered<br>Contractor Report |  |
|  |  |  |  | 14. Sponsoring Agency Code<br>RTOP 505-33-31               |  |
| 15. Supplementary Notes<br>Point of Contact: Technical Monitor, Dr. A. H. Heimbuch, M/S 223-6<br>Ames Research Center, Moffett Field, CA 94035<br>(415) 965-6274 or FTS 448-6274   |  |  |  |  |  |
| 16. Abstract<br><br><p>Vinystilbazole (vinylstyrylpyridine) and vinylpolystyrylpyridine were prepared for the purpose of modifying bismaleimide composite resins. Cure studies of resin systems were investigated by differential scanning calorimetry. The vinylstyrylpyridine-modified bismaleimide composite resins were found to have lower cure and gel temperatures, and shorter cure times than the corresponding unmodified composite resins. The resin systems were reinforced with commercially available satin-weave carbon cloth. Prepregs were fabricated by solvent or hot melt techniques. Thermal stability, flammability, moisture absorption, and mechanical properties of the composites (such as flexural strength, modulus, tensile and short beam shear strength) were determined. Composite laminates showed substantial improvements in both processability and mechanical properties compared to the bismaleimide control systems.</p> <p>The vinylstyrylpyridine modified bismaleimide resins can be used as advanced matrix resins for graphite secondary structures where ease of processing, fireworthiness and high temperature stability are required for aerospace applications.</p> |  |  |  |  |  |
| 17. Key Words (Suggested by Author(s))<br><br>Composite Laminates<br>Vinylpolystyrylpyridine<br>Bismaleimide resins  |  |  | 18. Distribution Statement<br><br>Unclassified - Unlimited<br><br>STAR Category 23 |  |  |
| 19. Security Classif. (of this report)<br>Unclassified   |  | 20. Security Classif. (of this page)<br>Unclassified |  | 21. No. of Pages<br>64                                     |  |
|  |  |  |  | 22. Price*<br>A04  |  |

# NOTICE

THIS DOCUMENT HAS BEEN REPRODUCED FROM THE BEST COPY FURNISHED US BY THE SPONSORING AGENCY. ALTHOUGH IT IS RECOGNIZED THAT CERTAIN PORTIONS ARE ILLEGIBLE, IT IS BEING RELEASED IN THE INTEREST OF MAKING AVAILABLE AS MUCH INFORMATION AS POSSIBLE.

|                          |                                     |
|--------------------------|-------------------------------------|
| Accession For            |                                     |
| NTIS GRA&I               | <input checked="" type="checkbox"/> |
| DTIC TAB                 | <input type="checkbox"/>            |
| Unannounced              | <input type="checkbox"/>            |
| Justification            |                                     |
| <i>printout enclosed</i> |                                     |
| <i>one as memo</i>       |                                     |
| By <i>2 Nov 95</i>       |                                     |
| Distribution/            |                                     |
| Availability Codes       |                                     |
| Dist                     | Avail and/or Special                |
| <i>A-1</i>               |                                     |

NASA CONTRACTOR REPORT 166595

Development of New and Improved Polymer Matrix  
Resin Systems (Phase I)

M. S. Hsu

Prepared for  
Ames Research Center  
under Contract NAS2-11529



National Aeronautics and  
Space Administration

**Ames Research Center**  
Moffett Field, California 94035



HC Chem Research & Service, Corp.

Report No. 1001

DEVELOPMENT OF NEW AND IMPROVED POLYMER  
MATRIX RESIN SYSTEMS (PHASE I)

FINAL REPORT

by

Ming-ta S. Hsu

Contract No. NAS2-11529

To: NASA Ames Research Center  
Chemical Research Projects Office  
Moffett Field, CA 94035  
Technical Monitor: Dr. A. H. Heimbuch

December 1982 - December 1983

1-C

## FOREWORD

This Phase I final report covers the work performed under NAS2-11529 from the period December 20, 1982 to December 19, 1983. Dr. Alvin H. Heimbuch at NASA Ames Research Center was the Project Monitor. Dr. Ming-ta S. Hsu of HC Chem Research & Service, Corp. was the Program Manager and Principal Investigator. Support activity was provided by Dr. Timothy S. Chen and David R. Liu.

ABSTRACT

Vinylstilbazole (vinylstyrylpyridine) and vinylpolystyrylpyridine were prepared for the purpose of modifying bismaleimide composite resins. Cure studies of resin systems were investigated by differential scanning calorimetry. The vinylstyrylpyridine-modified bismaleimide composite resins were found to have lower cure and gel temperatures, and shorter cure times than the corresponding unmodified composite resins. The resin systems were reinforced with commercially available satin-weave carbon cloth. Prepregs were fabricated by solvent or hot melt techniques. Thermal stability, flammability, moisture absorption, and mechanical properties of the composites (such as flexural strength, modulus, tensile and short beam shear strength) were determined. Composite laminates showed substantial improvements in both processability and mechanical properties compared to the bismaleimide control systems.

The vinylstyrylpyridine modified bismaleimide resins can be used as advanced matrix resins for graphite secondary structures where ease of processing, fireworthiness and high temperature stability are required for aerospace applications.

TABLE OF CONTENTS

|        |   |    |
|--------|---|----|
| 1.     | INTRODUCTION .....  | 1  |
| 2.     | SYNTHESIS AND CHARACTERIZATION OF VINYLSTYRYLPYRIDINE.....                            | 4  |
| 2.1.   | Synthesis of Vinylstilbozale.....   | 4  |
| 2.2.   | Characterization of Vinylstilbozale.....  | 5  |
| 2.3.   | Synthesis of Vinylpolystyrylpyridine.....   | 6  |
| 2.4.   | Characterization of Vinylpolystyrylpyridine.....                                      | 7  |
| 3.     | CHEMICAL AND PHYSICAL PROPERTIES OF VINYLSTYRYLPYRIDINE<br>MODIFIED BISMALEIMIDE..... | 9  |
| 3.1.   | Copolymerization of VST and H795.....   | 9  |
| 3.2.   | Copolymerization of VPSP and H795.....  | 10 |
| 3.3.   | Thermogravimetric Analysis of Cured Resins.....                                       | 10 |
| 4.     | PREPREG AND LAMINATE PREPARATION.....   | 13 |
| 4.1.   | Prepreg Preparation.....  | 13 |
| 4.2.   | Cure Study of Prepreg.....  | 13 |
| 4.3.   | Laminate Preparation.....   | 15 |
| 4.3.1. | Molding Procedures.....   | 15 |
| 4.4.   | DMA Analysis of the Cured Laminate.....   | 15 |
| 4.5.   | Mechanical and Physical Properties of the Laminate.....                               | 16 |
| 4.6.   | Rubber Toughening Study.....  | 16 |
| 5.     | FACE SHEET PREPARATION FOR INTERIOR SANDWICH PANEL.....                               | 21 |
| 5.1.   | Material.....   | 21 |
| 5.2.   | Prepreg Preparation.....  | 21 |
| 5.2.1. | Specification for VPSP/H795KT148 Prepreg of Face Sheet<br>(Hot Melt Method).....      | 21 |
| 5.2.2. | Specification for VPSP/H795KT148 Prepreg of Face Sheet<br>(Wet Method).....           | 22 |
| 5.3.   | Face Sheet Molding Procedures.....  | 23 |
| 5.3.1. | Face Sheet Prepared from VPSP/H795 Resin Systems.....                                 | 23 |
| 5.3.2. | Face Sheet Made from H795 Resin.....  | 23 |
| 5.3.3. | Face Sheet Made form Epoxy Resin.....   | 23 |
| 5.4.   | Evaluation of Face Sheet.....   | 24 |
| 5.4.1. | Thermogavimetric Analysis.....  | 24 |
| 5.4.2. | Smoke Chamber Examination of Face Sheet.....  | 24 |

TABLE OF CONTENTS (CONTINUE)

|        |   |    |
|--------|---|----|
| 5.5.   | Preliminary Sandwich Panel Preparation.....           | 24 |
| 5.5.1. | Preliminary Sandwich Panel Preparation Procedure..... | 24 |
| 5.5.2. | Evaluation of Sandwich Panel.....                     | 25 |
| 6.     | PREPARATION OF DELIVERABLES.....                      | 29 |
| 7.     | CONCLUSIONS AND RECOMMENDATIONS.....                  | 30 |
| 8.     | REFERENCE.....  | 31 |

## 1. INTRODUCTION

Bismaleimides are being used increasingly as high-temperature matrix resins for graphite fiber-reinforced composites. The monomers are cured by a thermally induced addition reaction to give highly crosslinked, void-free network polymers having good physical properties with high char yield, and higher thermal stability, better fire resistance, and lower water absorption than state-of-the-art epoxy systems.<sup>(1)</sup> However, there are problems with maleimide polymers, such as solvent retention in the prepregs, and high temperature often required for curing,<sup>(2)</sup> and brittleness of the polymers due to the high crosslink density obtained in network polymers. Recently, Technochemie GmbH-Verfahrenstechnik developed a "hot-melt" solventless bismaleimide-type resin (H795)<sup>(3)</sup> to overcome the solvent retention problem, but this resin cures at a high temperature.

It is well known that vinyl monomers (such as styrene and divinylbenzene) readily copolymerize with maleimide double bonds at rather low temperatures (120-150°C). Vinyl monomers and a wide variety of vinylterminated oligomers are expected to act as reactive diluents or comonomers for bismaleimide resins. However, ordinary vinyl monomers would cause difficulties due to volatile losses and microvoid formation. If the vinyl linkage is in an aliphatic structure, the high-temperature performance of the modified maleimide polymer could be significantly decreased by depolymerization

and scission, thereby limiting the high temperature stability and reducing anaerobic char yield, and the flame-resistance.

It has been shown that graphite composites formulated from polystyrylpyridine matrix resins obtained from the condensation reaction of collidine and aromatic dialdehydes exhibit excellent fire resistance and high temperature stability.<sup>(4)</sup> Unfortunately, because the condensation curing reaction evolves water, void-free composites are difficult to obtain. Also, curing temperatures in excess of 250°C are required. At such high temperature, the matrix resin is stabilized by the presence and persistence of the vinylene double bond in the stilbazole moiety.

From model compound studies,<sup>(5)</sup> it appears that at temperatures in excess of 300°C the stilbazole group reacts in situ to give a highly crosslinked ring system, characterized by a char yield of 70% at 600-800°C in nitrogen. Advantage has been taken of these special thermal properties of the vinylene double bond in the design and synthesis of vinylstilbazole (VST) and vinylpolystyrylpyridine (VPSP) oligomers.

HC Chem Research & Service, Corp. has synthesized a vinyl terminated polystyrylpyridine (VPSP) and vinyl stilbazole (VST) by incorporating 5-vinyl-2-methyl pyridine with collidine and terephthalaldehyde, or by reacting 5-vinyl-2-methyl pyridine with benzaldehyde. Preliminary data indicated that the reaction product of VST and H795 has shown significant improvements on processibility.

The objectives of this contract are:

- (1) To study and improve the synthesis of vinylstilbazole (VST) and vinylpolystyrylpyridine (VPSP).
- (2) To process these materials together with H795 and to evaluate the ability of these materials to form prepregs.
- (3) To develop and evaluate the graphite composite panels, prepared with VST/VPSP and H795 in different ratios.
- (4) To develop a light weight face sheet made with vinylstyrylpyridine modified bismaleimide resin for fire resistant sandwich aircraft interior panel.



## 2. SYNTHESIS AND CHARACTERIZATION OF VINYLSTYRYLPYRIDINE OLIGOMERS

### 2.1. Synthesis of Vinylstilbazole (VST).

Vinylstilbazole, or vinylstyrylpyridine, was synthesized by the condensation reaction of benzaldehyde and 2-methyl-5-vinylpyridine (MVP) in the presence of acetic acid and acetic anhydride at 100-120°C. (Fig. 1). 5-vinyl-2-methyl pyridine is an unstable compound. A series of experiments have been carried out to study the stability and reactivity of 5-vinyl-2-methyl pyridine under different reaction conditions. It was found that 5-vinyl-2-methyl pyridine polymerized rapidly through its double bond at temperature above 140°C, therefore prolong heating at temperature at 140°C would result a lot of poly-5-vinyl-2-methyl pyridine and reduce the yield of vinyl-stilbazole. On the other hand, if reaction temperature was below 100°C, most of the 5-vinyl-2-methyl pyridine did not react with benzaldehyde and the yield of vinyl-stilbazole was reduced with too much unreacted starting materials.

A typical reaction for synthesis of vinyl-stilbazole was carried out as follows: (see flow chart in Fig. 2)

50.0g (0.42 mole) of 5-vinyl-2-methyl pyridine, 44.6g (0.42 mole) of benzaldehyde, 25.2g (0.42 mole) of acetic acid, and 42.9g (0.42 mole) of acetic anhydride were placed in a 1000 ml, 3-necked round-bottom flask equipped with a mechanical stirrer and reflux condenser. The flask was immersed in an oil bath with a temperature control unit. The

reaction solution was deoxygenated by nitrogen for 30 min.. The reaction solution was heated to 110°C and held at this temperature for seventy-two hours. The reaction solution was then allowed to cool to room temperature and poured into a large beaker containing 1000 ml of 10% sodium hydroxide solution. The mixture was stirred for half an hour and the aqueous layer was decanted. The brownish viscous product was washed several times with de-ionized water until the water layer tested neutral. All the water was then discarded by decantation and the product was dissolved in 400 ml tetrahydrofuran (THF). The THF filtrate was then poured into large quantity of de-ionized water to precipitate out vinyl-stilbazole. This purification was repeated at least three times. Finally the brownish product was dried in vacuum, weighed and transferred into a storage container with or without THF as solvent.

## 2.2. Characterization of Vinyl-stilbazole

The synthesized vinylstilbazole was a low melting solid which contained some oligomers of VST. The infrared spectrum (Fig. 3) and nuclear magnetic resonance spectrum (Fig. 4) of the synthesized vinylstilbazole (HC 202) showed that it also contained some acetate and aliphatic hydrogens, and trace amount of unreacted starting materials. The acetate was derived from the acetic acid-acetic anhydride as acetate salt which was hard to remove by washing with water and base. The aliphatic hydrogens probably were derived from the addition product of the vinyl group.(oligomers of VST)

The dried material was also analyzed with mass spectrometry by means

of direct insertion probe. The total ion intensity versus temperature (or time) is shown in Fig. 5. The major product was vinylstilbazole at 3.3 min.. Mass spectrum of the major product is shown in Fig. 6. Minor products were dimer of vinylstilbazole (m/e 413, M-1) and adduct of vinylstilbazole and 5-vinyl-2-methyl pyridine (m/e 325, M-1). Trace amount of starting materials were present in the dried crude product. Pure vinylstilbazole was isolated from the crude product by column chromatography packed with silica gel and eluted with chloroform/hexane= 1/4 mixture. The isolated solid was then recrystallized from methanol-water to give a light yellow crystalline pure VST. with a m.p. of 60°C. IR and NMR of the pure VST are shown in Fig. 7 and 8 respectively.

### 2.3. Synthesis of Vinylpolystyrylpyridine

It was reported that vinylpolystyrylpyridine (VPSP) could be prepared by reacting collidine, terephthalaldehyde and 2-methyl-5-vinyl pyridine in the presence of acetic anhydride and acetic acid at a temperature of 115°C to 120°C for 24 hours.<sup>(6)</sup> The same one step procedure was attempted to make VPSP. The resulting VPSP was a solid which was not very soluble in THF and had a softening temperature above 120°C. A two step process for preparing VPSP oligomers was developed (Fig. 9) to give a better VPSP product. The first step was to synthesize prepolymer of polystyrylpyridine (PSP) by reacting collidine with terephthalaldehyde at 150-170°C for a short period of time. The second step was the reaction of PSP prepolymer with MVP at low temperature (100-120°C) to avoid polymerization of MVP starting material and VPSP product. The resulting VPSP is soluble in THF and melts (softens) at about 100°C. A typical

reaction for synthesis of vinylpolystyrylpyridine was carried out as follows:

18.0g (0.3 mole) of acetic acid, 30.6g (0.3 mole) of acetic anhydride, 20.1g (0.15 mole) of terephthalaldehyde, and 12.1g (0.1 mole) of collidine were placed in a 500 ml, 3-necked round bottom flask equipped with a mechanical stirrer and a reflux condenser. After the reaction solution was deoxygenated, the flask was immersed in an oil bath and the reaction solution was heated at  $150^{\circ}\text{C}$  to  $170^{\circ}\text{C}$  for 4 to 6 hours. The reaction solution was cooled to room temperature and 17.9g (0.15 mole) of 5-vinyl-2-methyl pyridine was added. The solution was degassed again and heated to  $100^{\circ}\text{C}$ - $120^{\circ}\text{C}$  for 48 hours. The reaction mixture was then poured into 10% NaOH solution. The brownish viscous product was washed with 10% NaOH solution, then with de-ionized water until the aqueous layer tested neutral. All the water was decanted and the product was dissolved in THF and filtered. The filtrate was then poured into large quantity of de-ionized water to precipitate out VPSP. This purification was repeated several times. Finally the product was dried in vacuum and stored as dry solid or in THF.

#### 2.4. Characterization of Vinylpolystyrylpyridine

Vinylpolystyrylpyridine (VPSP) oligomer was characterized by infrared (IR) and nuclear magnetic resonance (NMR) spectrometry. Fig. 10 shows the infrared spectrum of VPSP. The aromatic C-H stretching is at  $3000\text{-}3100\text{ cm}^{-1}$ . The carbonyl absorptions at  $1750$  and  $1700\text{ cm}^{-1}$  are for acetate and unreacted aldehyde, respectively. The C=C stretching is in the  $1600\text{ - }1450\text{ cm}^{-1}$  region. Methyl bending is at  $1380\text{ cm}^{-1}$ .

Trans stilbazole double bond bending is at  $970\text{ cm}^{-1}$ . Vinyl double bond bending is at  $910\text{ cm}^{-1}$ . NMR spectrum of VPSP in chloroform is shown in Fig. 11. Unreacted aldehyde proton is at 9.9 ppm. The aromatic and internal olefinic protons are at 6.4 - 8 ppm. Vinyl protons are at 5 - 6 ppm. The peak at 4.6 ppm is due to the trace amount of water present in the sample. The region between 2 - 3 ppm is due to methyl group resonance of acetate and collidine. The peaks at 3.7 and 1.8 ppm are due to tetrahydrofuran which was present in the sample.

Molecular weight of VPSP samples were measured using a Water Associates Model 202 Gel Permeation Chromatograph (GPC). The experimental conditions were as follows: Solvent, tetrahydrofuran; temperature, ambient; column, DuPont PSM 60S; sample concentration, 1%; flow rate, 1 ml/min; detector; refractive index. Fig. 12 is the GPC curve for a typical VPSP sample. The weight average molecular weight ( $M_w$ ) was 3500, the number average molecular weight ( $M_n$ ) was 950 using polystyrene standard curve multiplied with a factor of 1.5. The factor of 1.5 was derived by using 1,6-distyrylpyridine and 1,4,6-tristyrylpyridine standards.

### 3. CHEMICAL AND PHYSICAL PROPERTIES OF VINYLSTYRYLPYRIDINE-MODIFIED BISMALIMIDE

Two batches of hot-melt H795 bismaleimide were supplied by NASA-Ames. The first batch M1268 cures at a temperature of 240-280°C. The second batch KT-148 cures at a lower temperature of 200-240°C. The differential scanning calorimetry (DSC) of the two batches are shown in Fig. 13 and 14 respectively. H795-KT148 contains some solvent (toluene) and starts to melt at about 70°C. H795-M1268 melts at about 120°C.

#### 3.1. Copolymerization of VST and H795

Both VST and VPSP were easily thermally copolymerized with the hot-melt bismaleimide H795 over a wide range of comonomer ratios. Typical thermal processes occurring during copolymerizations are shown in the differential scanning calorimeter traces for VST and H795-M1268 in Fig. 13. It can be seen that VST exhibits a DSC melting temperature of 40-70°C with a slow and weak exothermic curing reaction occurring over a temperature range of 160-240°C due to thermal polymerization of the vinyl double bond of VST. In separate thin film infrared studies, it was found that the stilbazole double bond does not participate in that reaction. However, polymerization of the latter double bond probably occurs at higher temperature as suggested by the mild exotherm above 320°C. The DSC for H795 shows an endothermic melting point around 120°C, and a DSC cure temperature of 261°C typical of aromatic bismaleimides. The higher the VST/H795 weight ratio, the lower is the cure temperature until the optimum 1:1 weight ratio is reached. It can be seen that the blend with a VST/H795

weight ratio 1:4 (mole ratio of 1:2) begins to melt around 50°C and then polymerizes rapidly at 166°C; a cure temperature some 100°C below that of H795 alone. When blend has a weight ratio of 3:7, the polymerization temperature decreases to 159°C which is probably the temperature for a reaction of the vinyl group with the maleimido group. Similar reductions in melting points and cure temperatures are seen with VST/H795-KT148 (Fig. 14). Different batches of VST may show slightly different but similar DSC cures for the copolymer.

### 3.2. Copolymerization of VPSP and H795

Typical copolymerization of VPSP and H795 are shown in the DSC traces for VPSP/H795-M1268 blends in Fig. 15. VPSP melts around 80-130°C, the exotherm peak around 180°C is due to the addition reaction of vinyl group. The VPSP/H795-M1268 mixture melted around 100°C and then polymerized between 160-280°C depending on the amount of VPSP in the mixture, the more the amount of VPSP in the mixture the lower the cure temperature. Vinyl content of VPSP was very important, the higher the vinyl content the lower the cure temperature for the copolymer. Similar DSC curves were observed for VPSP/H795KT148 blends as shown in Fig. 16.

### 3.3. Thermogravimetric Analysis of Cured Resins

Thermogravimetric analysis (TGA) of cured H795, VST/H795, and VPSP/H795 blends was carried out in nitrogen and in air at 10°C/min.. Typical

TGA curves in nitrogen and in air are shown in Fig. 17 and 18 respectively. All resins decomposition temperatures are the same in nitrogen and in air. There is no char in air at temperatures above 600°C for all the resins tested.

The results obtained from thermochemical-physical characterization of H795 and copolymers are compared in Table 1. In all the copolymer ratios investigated, the cure temperatures are significantly reduced below that for the bismaleimide itself, and are less than that typically obtained for aerospace grade epoxy resin. The anaerobic thermal stability is as good as that of bismaleimide alone, as indicated by polymer decomposition temperatures in excess of 420°C. As predicted from studies on other stilbazole polymers, the anaerobic char yields are significantly higher than those obtainable from aerospace grade epoxy resins. With the exception of the VST/H795 ratio of 3:7, all the char yields for the various copolymers are substantially greater than that for the H795 bismaleimide alone. It is likely that the copolymer with the 3:7 ratio has too low a crosslink density to achieve an optimum char yield.



TABLE 1: THERMOCHEMICAL-PHYSICAL PROPERTIES OF  
BISMALEIMIDE AND COPOLYMERS

| RESIN SYSTEM        | CURE TEMPERATURE<br>(DSC PEAK), °C | T <sub>g</sub> , °C | PDT<br>(N <sub>2</sub> ), °C | CHAR YIELD<br>at 800°C, % |
|---------------------|------------------------------------|---------------------|------------------------------|---------------------------|
| EPOXY (MY720-DDS)   | 255                                | 250                 | 300                          | 30                        |
| BISMALEIMIDE (H795) | 261                                | > 400               | > 420                        | 42                        |
| COPOLYMERS:         |                                    |                     |                              |                           |
| VST:H795 = 1:9      | 205                                | 380                 | > 420                        | 42                        |
| VST:H795 = 1:4      | 166                                | 380                 | > 420                        | 43                        |
| VST:H795 = 3:7      | 159                                | 380                 | > 420                        | 36                        |
| VPSP:H795 = 1:9     | 223                                | > 400               | > 420                        | 43                        |
| VPSP:H795 = 1:4     | 211                                | > 400               | > 420                        | 50                        |
| VPSP:H795 = 3:7     | 195                                | > 400               | > 420                        | 55                        |
| VPSP:H795 = 2:3     | 175                                | > 400               | > 420                        | 56                        |

H795 is H795 M1268

#### 4. PREPREG AND LAMINATE PREPARATION

A prepreg can be prepared by hot-melt or wet method using THF as a solvent. Viscosity data for H795 and copolymers are shown in Table 2.

##### 4.1. Prepreg Preparation

Our prepregs were prepared by coating graphite cloth (8 harness satin weave cloth) with a THF solution of the resin. The prepregs were dried in an air oven at 80°C for 20 min.. The prepreg should be stored at -10°C to 15°C. The resin content of the prepreg should be 35±5% and volatile content less than 5%.

##### 4.2. Cure Study of Prepreg

Isothermal cure study of the dried prepregs was performed using a Du Pont 981 dynamic mechanical analyzer. Isothermal DMA curves are shown in Fig. 19 and 20, with stiffness (modulus) of the prepreg plotted as a function of time at different temperatures. It is seen that the copolymers cure at a lower temperature and for a shorter time than does the bismaleimide H795-M1268. Similar DMA curves are shown in Fig. 21 - 23 for H795KT148 and modified H795KT148 at different isothermal temperatures, once again H795KT148 cures at lower temperature and shorter time than H795M1268. The modified resins also cure at lower temperature and shorter time than the bismaleimide alone. The resin blend of VPSP and H795 with the weight ratio of 3 to 7 is likely to be the selected matrix resin for advanced composite due to its high char yield in nitrogen. At the same isothermal temperature, the prepreg made

Table 2 VISCOSITY OF H795 AND COPOLYMERS

| MATERIALS   | MELTING POINT | VISCOSITY,cps  |
|---|---------------|--|
| H795 M1268  | 140 - 120°C   | 400 - 500 at 120°C<br>400 - 500 after 1 hr at 120°C                            |
| H795 KT148  | 70 - 100      | 2500 - 3000 at 100°C   |
| VST 1 part<br>H795 M1268, 4 parts                   | 70 - 100      | 11,000 at 105°C<br>32,000 after ½ hr at 105°C                                  |
| VPSP, 3 parts<br>H795 M1268, 7 parts                | 70 - 100      | 3000 at 100°C<br>9000 after ½ hr at 100°C                                      |
| VST 3 parts<br>H795 M1268, 4 parts<br>THF 5 parts   |               | 10 - 50 at ambient   |
| VPSP 3 parts<br>H795 M1268, 7 parts<br>THF 10 parts |               | 10 - 50 at ambient   |
| VPSP 3 parts<br>H795 KT148, 7 parts<br>THF 1 part   |               | 3000 - 5000 at 70°C<br>5000 - 10000 ½ hr at 70°C<br>10000 - 16000 1 hr at 70°C |

with VPSP modified H795 (3:7) can be cured even faster than VST modified H795 (1:4) as shown in Fig. 22 and 23.

#### 4.3. Laminate Preparation

The dried prepreg (4 or 9 plies) was stacked and pressed between aluminum plates covered with Teflon film. The laminate was then cured in a flat platen press at 200°C at a pressure of 75-100 psi for 3.5-4 hr. Postcure of the laminate was not performed. Typical laminate preparation is shown in the molding procedure for VPSP/H795 resin.

##### 4.3.1. Molding Procedures

- a. In a flat platen load material at room temperature, apply contact pressure and heat to 160°C.
- b. After 20 min, at 160°C, heat to 180°C and apply 75 psi for 10 min.
- c. Heat to 200°C and 100 psi for 4 hrs.
- c. Cool under pressure.

#### 4.4. DMA Analysis of the Cured Laminate

Modulus curves of VST, VPSP modified and unmodified bismaleimide laminates are compared with MY720/DDS epoxy system as shown in Fig. 24. The bismaleimide H795M1268 sample was not completely cured, as indicated by the modulus dip in the temperature range of 100-300°C. However, the cure was completed after this was heated to 300°C. (The cure was completed under the same conditions as those for the copolymers which showed no modulus dip in the DMA curves.) From Fig. 24, it appears that the glass transition temperature of bismaleimide and copolymers is above 380°C, or

130-150°C higher than the glass transition temperature (~250°C) of epoxy resin.

#### 4.5. Mechanical and Physical Properties of the Laminate

The laminates were tested for a number of physical properties: short beam shear (ASTM D 2344-76), flexural strength (ASTM D 790-70), and tensile strength (ASTM D 638-68). The flammability tests were performed with a Stanton-Redcroft Flammability Unit and the LOI was determined according to ASTM D 2863-74. The results are shown in Table 3. The flammability (LOI) of the composites based on the copolymers is equal to or better than that of the bismaleimide alone. In Table 3, it is also seen that the copolymers give better mechanical properties than the bismaleimide alone. The superior mechanical properties of the copolymers are probably due to the completion of the crosslinking reaction and/or better control on crosslinking density. The values for water absorption amounts to 1% or less. It was found that a comparable epoxy-graphite composite usually gives 2-3% water absorption under similar conditions. One may expect substantial improvement in the hot wet strength of these composites. Mechanical properties of laminate composite made with H795KT148 and modified H795KT148 are shown in Table 4.

#### 4.6. Rubber Toughening Study

Laminates using VST/H795 and VPSP/H795 resins modified with liquid rubber CTBN have been prepared. Some mechanical properties of the composites made from CTBN modified resins have been measured. The mechanical properties of the composites were improved slightly by adding CTBN in the resin matrix as shown in Table 5. Thermogravimetric analysis of cured

TABLE 3 MECHANICAL PROPERTIES OF VST, VPSP/H795 COPOLYMER  
COMPARED WITH H795 GRAPHITE COMPOSITES

| PHYSICAL & MECHANICAL<br>PROPERTIES       | RESIN SYSTEM WITH 9 PLY SATIN-WEAVE GRAPHITE FIBER |                  |                 |                  |                 |             |
|---|--|------------------|-----------------|------------------|-----------------|-------------|
|   | H795   | VPSP/H795<br>1:4 | VST/H795<br>1:4 | VPSP/H795<br>3:7 | VST/H795<br>3:7 | VPSP        |
| RESIN CONTENT, %                          | 30.5   | 26               | 30              | 30.2             | 31.5            | 26          |
| DENSITY, g/cc                             | 1.55   | 1.43             | 1.39            | 1.4              | 1.39            | 1.44        |
| LOI (4 PLY SAMPLE)                        | 52   | 62               | 46              | 55               | 45              | 57          |
| WATER ABSORPTION, %<br>2 hr BOILING WATER | 0.72   | 1.17             | 0.99            | 1.20             | 0.86            | 1.36        |
| SHORT BEAM SHEAR<br>R.T. $N/mm^2$ (KSI)   | 11.7 (1.7)   | 20.5 (2.95)      | 20.4 (2.96)     | 18.8 (2.7)       | 19.9 (2.89)     | 21.7 (3.15) |
| R.T. FLEXURAL<br>MODULUS, $KN/mm^2$ (msi) | 53 (7.7)   | 54.5 (7.9)       | 50 (7.3)        | 51 (7.4)         | 51 (7.4)        | 42.4 (7.6)  |
| STRENGTH, $N/mm^2$ (ksi)                  | 166 (24)   | 337.9 (49)       | 317 (46)        | 331 (48)         | 282 (41)        | 337.9 (49)  |
| ENERGY, ft. lb                            | 3.1  | 8.3              | 8.8             | 8.7              | 7.3             | 12          |
| R.T. TENSIL<br>STRENGTH, $N/mm^2$ (ksi)   | 248 (36)   | 344.8 (50)       | 289.7 (42)      | 386.2 (56)       | 275.8 (40)      | 406.9 (59)  |
| MODULUS, $KN/mm^2$ (msi)                  | 13.8 (2.0)   | 15.2 (2.2)       | 17.2 (2.5)      | 16.6 (2.4)       | 11.7 (1.7)      | 15.9 (2.5)  |
| ELONGATION-YIELD, %                       | 2.3  | 4.5              | 3.3             | 4.9              | 3.9             | 4.7         |

\*H795 is H795M1268

Table 4 PHYSICAL AND MECHANICAL PROPERTIES OF BMI (H795 KT148) and VST/VPSP MODIFIED  
BMI GRAPHITE FIBER COMPOSITE

| PROPERTIES  | RESIN SYSTEM WITH 8 HARNESS SATEN WEAVE GRAPHITE FIBER |                    |                    |                   |
|---|--|--------------------|--------------------|-------------------|
|   | H795 KT148   | VPSP/H795KT148=1/4 | VPSP/H795KT148=3/7 | VST/H795KT148=1/4 |
| RESIN CONTENT, %                                    | 22   | 22.5               | 22                 | 25.5              |
| DENSITY, g/ml                                       | 1.54   | 1.53               | 1.58               | 1.48              |
| CHAR YIELD AT 800°C in N <sub>2</sub> , %           | 48.5   | 52                 | 51                 | 47                |
| LOI, %  | 59   | 65                 | 63                 | 50                |
| SHORT BEAM SHEAR, R.T.<br>N/mm <sup>2</sup> (ksi)   | 15.2(2.2)  | 17.1(2.48)         | 16.6(2.41)         |                   |
| FLEXURAL, R.T.<br>STRENGTH, N/mm <sup>2</sup> (ksi) | 283(41)  | 276(40)            | 297(43)            | 393(57)           |
| MODULUS, KN/mm <sup>2</sup> (msi)                   | 63.4(9.2)  | 62.8(9.1)          | 62(9.0)            | 64.8(9.4)         |
| ENERGY, Ft-Lb                                       | 8.7  | 8.7                | 7.8                | 11.8              |
| TENSILE, R.T.<br>STRENGTH, N/mm <sup>2</sup> (ksi)  | 531(77)  | 551(80)            | 517(75)            |                   |
| MODULUS, KN/mm <sup>2</sup> (msi)                   | 19.3(2.8)  | 17.9(2.6)          | 17.9(2.6)          |                   |
| ELONGATION %  | 4.5  | 4.5                | 3.5                |                   |

ORIGINAL PAGE IS  
OF POOR QUALITY

Table 5 PRELIMINARY PROPERTIES OF LIQUID RUBBER MODIFIED GRAPHITE FIBER COMPOSITE

| PROPERTIES   | RESIN SYSTEM WITH 8 HARNESS SATIN WEAVE GRAPHITE FIBER |                         |                  |                         |                        |
|--|--|-------------------------|------------------|-------------------------|------------------------|
|  | VST/H795/CTBN<br>2/7/1                                 | VPSP/H795/CTBN<br>2/7/1 | H795/CTBN<br>9/1 | VPSP/H795/CTBN<br>2/8/1 | VST/H795/CTBN<br>2/8/1 |
| RESIN CONTENT, %   | 29.8   | 27.5                    | 24               | 23                      | 24                     |
| CHAR YIELD, %<br>at 800°C in N <sub>2</sub>                    | 37   | 40                      | 37               | 35                      | 35                     |
| FLEXURAL, R.T.<br>STRENGTH, N/mm <sup>2</sup> (ksi)            | 327(47.3)  | 327(47.4)               | 461(66.9)        | 397(57.3)               | 410(58.3)              |
| MODULUS, KN/mm <sup>2</sup> (msi)                              | 53 (7.7)   | 56 (8.2)                | 67 (9.7)         | 58 (8.5)                | 58 (8.4)               |
| ENERGY, FT-LB  | 10.38  | 11.18                   | 13.96            | 11.99                   | 14.51                  |
| SHORT BEAM SHEAR, R.T.<br>N/mm <sup>2</sup> (ksi)              | 19.8(2.75)   | 19.4(2.82)              | 19.9(2.89)       | 17.4(2.52)              | 21.6(3.13)             |
| TENSILE, R.T. <sup>2</sup><br>STRENGTH N/mm <sup>2</sup> (ksi) |  |                         | 317(46)          | 310(45)                 | 317(46)                |
| MODULUS KN/mm <sup>2</sup> (msi)                               |  |                         | 13.1(1.9)        | 13.8(2.0)               | 15.2(2.2)              |
| ELONGATION-YIELD   |  |                         | 3.5              | 3.2                     | 3.0                    |

\*H795 is H795M1268



CTBN modified resins have been determined in nitrogen at a heating rate of  $10^{\circ}\text{C}/\text{min}..$  The char yield at  $800^{\circ}\text{C}$  for resins with CTBN was lower than those without CTBN reported previously. The less than 40% char yield of CTBN modified resins indicated that composite made from these resins may have poor fire resistance property.

## 5. FACE SHEET PREPARATION FOR INTERIOR SANDWICH PANEL

### 5.1. Material

It has been found that VPSP/H795 resin mixture with the weight ratio of 3 to 7 could be cured at a much lower temperature than H795 resin alone and also gave a composite with reasonably good physical and mechanical properties. This resin system has high char yield and good flame resistance property. Since H795KT148 cures at lower temperature than H795M1268, H795KT148 was used for face sheet preparation. Large scale synthesis of VPSP was performed by American Cyanamid according to our synthetic procedure, VPSP (Batch 179) was used for the face sheet preparation. Light weight carbon fiber (Hercules-A193A) was used for the face sheet. Some face sheet was also made with VPSP/H795 = 4/6 resin mixture.

### 5.2. Prepreg Preparation

Prepreg can be prepared by either hot-melt or wet method. The wet method was used for prepreg preparation. 10% solvent can be added in the resin system to improve the flow property for the hot-melt method.

#### 5.2.1. Specification for VPSP/H795KT148 Prepreg of Face Sheet (Preliminary suggested Hot-melt Method)

##### 1. Formulation of Prepreg Resin:

|  |          |
|--|----------|
| Part A. Vinyl polystyrylpyridine resin | 30 parts |
| Part B. Bismaleimide, H795             | 70 parts |
| Part C. Tetrahydrofuran                | 10 parts |

##### 2. Properties of formulation

Viscosity, Brookfield LVT, spindle #4

at 70 degree C

3,000-5,000 cps

|                   |               |     |
|-------------------|---------------|-----|
| half hour at 70°C | 5,000-10,000  | cps |
| one hour at 70°C  | 10,000-16,000 | cps |

3. Preparation of prepreg

- Coat carbon fiber (A193 P) by conventional hot melt method at 70°C.
- Dry coated fiber at 80°C for 15 min.
- Cool coated fiber to room temperature.
- Store prepregs at -10 to 5°C in a plastic bag.
- Resin content should be 45-50% and volatile content less than 5%.

5.2.2. Specification for VPSP/H795KT148 Prepreg of Face Sheet  
(Wet Method)

1. Formulation of Resin/Varnish:

|  |              |
|--|--------------|
| Part A. Vinylpolystyrylpyridine Resin (VPSP) | 30 parts     |
| Part B. Bismaleimide Resin (H795 KT148)      | 70 parts     |
| Part C. Tetrahydrofuran                      | 70-150 parts |

2. Properties of Formulation

|                                       |                |
|---------------------------------------|----------------|
| Viscosity, Brookfield LVT, #3, 60 rpm | 50-1000 cps    |
| Weight per gallon                     | 8.5-9.5 lb/gal |

3. Preparation of Prepreg

- Coat carbon fibers (A193 P) with varnish
- Dry coated fiber for 60 min. at 25°C, coat the carbon fiber again, dry the coated fiber at 25°C for 60 min.
- Dry the prepreg overnight at room temperature or 15 min. at 80°C.
- Store prepreg at -10 to 5°C in a plastic bag.
- Resin content should be 45-50% and volatile content less than 5%.

### 5.3. Face Sheet Molding Procedures

#### 5.3.1. Face Sheet prepared from VPSP/H795 resin systems

The molding procedures for face sheet made from VPSP/H795 resin systems are:

- a. In a flat polished platen load one ply prepreg (place one layer of release paper between platen and prepreg) at room temperature.
- b. Apply 100 psi, heat to 160-200°C, then hold for 1 - 3 hrs.
- c. Cool to room temperature slowly.
- d. Resin content should be 30 - 40%.

#### 5.3.2. The Molding Procedures for Face Sheet Made from H795 Resin

The following procedures was used to make H795 control face sheet.

- a. In a flat polished platen load one ply prepreg (place one layer of release paper between platen and prepreg) at room temperature.  
Apply contact pressure and heat to 160°C for 10 min.
- b. Apply 100 psi, heat to 180°C and hold for 1 - 3 hrs.
- c. Cool to room temperature slowly.
- d. Resin content should be 30-40%.

#### 5.3.3. Face Sheet Made from Epoxy Resin

Face sheet using epoxy resin (MY720-DDS) was also prepared by the procedure described in 5.3.1.. The face sheet prepared by this procedure had low resin content and there were holes in the cured sheets. The best condition to mold the epoxy face sheet has not been achieved.

#### 5.4. Evaluation of Face Sheet

##### 5.4.1. Thermogravimetric Analysis

Various resin face sheets with or without postcure were examined by TGA in nitrogen at different heating rates. The results are shown in Table 6 and 7 for 177°C (350°F) cured resin and molded face sheet respectively.

##### 5.4.2. Smoke Chamber Examination of Face Sheet

3" x 3" face sheet was placed in a smoke chamber and heated with 2.5 and 5 w/cm<sup>2</sup> heat flux. Mass change(% weight loss) and smoke density(DS) were measured. Mass optical density(DSMS=  $\Delta D_s / \Delta \text{mass}$ ), which is a correlating parameter for the NBS smoke density chamber<sup>7</sup>, was also reported. The results for the face sheets made with VPSP/H795 (3/7,4/6), H795KT control and base line epoxy resins are shown in Figs. 25-33. The data indicated that face sheet made with VPSP/H795(3/7) resin gave lower weight loss, smoke density and DSMS than those made with VPSP/H795=4/6, H795 bismaleimide control or base line epoxy resin.

#### 5.5 Preliminary Sandwich Panel Preparation

Sandwich panel was prepared by heating and pressing the face sheet, bond ply and honeycomb core together. Preparation of small 3"x3" panels using VPSP/H795, VST/H795 or H795 prepreg as adhesive has been attempted. The peel strength of the resulted panels was very weak. A small sandwich panel using Hysol LR100-349 as adhesive has shown good peel strength between face sheet and honeycomb core.

##### 5.5.1. Preliminary Sandwich Panel Preparation Procedure

1. Fabricate the sandwich panel according to the construction shown in the following figure.

\_\_\_\_\_ Cured face sheet

\_\_\_\_\_ Adhesive (FM 34-B18, American Cyanamid,  
or Hysol LR100-349, Dexter-Hysol)



Honeycomb core, HRH10,  
Nomex-Phenolic, 0.25"  
thick (Hexel)

\_\_\_\_\_ Adhesive

\_\_\_\_\_ Cured face sheet

2. Panels shall be cured for a minimum of 1 hr at 177°C (350°F) under a vacuum pressure of 50.8 cm-Hg (20 in-Hg) or 25 psi.
3. Cool the panel slowly to room temperature.
4. Weight of the finished panel was 110 - 150 g/ft<sup>2</sup>, which was less than the required 170 g/ft<sup>2</sup>.

#### 5.5.2. Evaluation of Sandwich Panel

Evaluation of sandwich panel will be the effort of Phase II of this contract.

Table 6 THERMOGRAVIMETRIC ANALYSIS OF VARIOUS RESINS FOR FACE SHEET IN N<sub>2</sub>. -26-

| RESIN & CURE METHOD   | HEATING RATE | DECOMPOSE TEMP. | CHAR YIELD (%) |
|---|--------------|-----------------|----------------|
| H795KT148 cured at 177°C<br>for 3 hrs   | 10 °C/min    | 423°C           | 44.5           |
|   | 50           | 427             | 41.5           |
|   | 100          | 450             | 41.2           |
| H795KT148 cured at 177°C<br>for 3 hrs<br>plus 5 hrs post cure<br>at 200°C           | 10           | 425             | 45.1           |
|   | 50           | 446             | 41.3           |
|   | 100          | 442             | 41.0           |
| H795KT148 cured at 177°C<br>for 3 hrs<br>plus 5 hrs post cure<br>at 250°C           | 10           | 408             | 47.0           |
|   | 50           | 437             | 46.0           |
|   | 100          | 435             | 44.3           |
| H795KT148 cured at 177°C<br>for 3 hrs<br>plus 5 hrs post cure<br>at 300°C           | 10           | 420             | 47.5           |
|   | 50           | 468             | 45.4           |
|   | 100          | 475             | 42.3           |
| H795KT148/VPSP(7:3)<br>cured at 177°C for 3 hrs                                     | 10           | 404             | 47.5           |
|   | 50           | 439             | 44.9           |
|   | 100          | 456             | 49.3           |
| H795KT148/VPSP(7:3)<br>cured at 177°C for 3 hrs<br>plus 5 hrs post cure<br>at 200°C | 10           | 399             | 54.2           |
|   | 50           | 458             | 52.6           |
|   | 100          | 560             | 50.5           |
| H795KT148/VPSP(7:3)<br>cured at 177°C for 3 hrs<br>plus 5 hrs post cure<br>at 250°C | 10           | 397             | 55.4           |
|   | 50           | 415             | 53.6           |
|   | 100          | 430             | 55.0           |
| H795KT148/VPSP(7:3)<br>cured at 177°C for 3 hrs<br>plus 5 hrs post cure<br>at 300°C | 10           | 418             | 58.1           |
|   | 50           | 450             | 55.4           |
|   | 100          | 438             | 55.3           |

Table 6 (continue)

| RESIN & CURE METHOD  | HEATING RATE | DECOMPOSE TEMP | CHAR YIELD % |
|--|--------------|----------------|--------------|
| H795KT148/VST, cured at<br>177°C for 3 hrs<br>(7:3)                                | 10 °C/min    | 370°C          | 38.8         |
|  | 50           | 407            | 36.7         |
|  | 100          | 405            | 38.2         |
| H795KT148/VST, cured at<br>177°C for 3 hrs, plus 5 hrs<br>post cure at 200°C (7:3) | 10           | 386            | 44.6         |
|  | 50           | 421            | 40.0         |
|  | 100          | 426            | 36.4         |
| H795KT148/VST, cured at<br>177°C for 3 hrs, plus 5 hrs<br>post cure at 250°C (7:3) | 10           | 386            | 45.0         |
|  | 50           | 436            | 38.9         |
|  | 100          | 427            | 38.3         |
| H795KT148/VST, cured at<br>177°C for 3 hrs, plus 5 hrs<br>post cure at 300°C (7:3) | 10           | 400            | 45.3         |
|  | 50           | 430            | 53.0         |
|  | 100          | 455            | 54.9         |
| MY720 - DDS, cured at 177°C<br>for 5 hrs.  | 10           | 335            | 26.4         |
|  | 50           | 381            | 19.6         |
|  | 100          | 394            | 22.8         |
| MY720 - DDS, cured at 177°C<br>for 5 hrs, plus 5 hrs post<br>cure at 200°C         | 10           | 328            | 32.7         |
|  | 50           | 385            | 27.4         |
|  | 100          | 417            | 25.1         |
| MY720 - DDS, cured at 177°C<br>for 5 hrs, plus 5 hrs post<br>cure at 250°C         | 10           | 341            | 36.1         |
|  | 50           | 393            | 31.6         |
|  | 100          | 400            | 29.5         |
| MY720 - DDS, cured at 177°C<br>for 5 hrs, plus 5 hrs post<br>cure at 300°C         | 10           | 320            | 47.0         |
|  | 50           | 385            | 46.5         |
|  | 100          | 392            | 43.4         |



Table 7 THERMOGRAVIMETIC ANALYSIS OF VARIOUS FACE SHEET (CURED) IN N<sub>2</sub>.

-28-

| FACE SHEET NO. | RESIN                            | CURE METHOD               | RESIN CONTENT | DECOMPOSE TEMPERATURE °C | CHAR YIELD % |
|----------------|----------------------------------|---------------------------|---------------|--------------------------|--------------|
| FS5E           | H795 KT                          | 3 hrs at 177°C            | 45.71%        | 434.5                    | 70.8         |
| "              | "                                | +5 hrs post cure at 200°C | 43.84         | 419                      | 71.3         |
| "              | "                                | +5 hrs post cure at 250°C | 51.11         | 428                      | 68.5         |
| "              | "                                | +5 hrs post cure at 300°C | 45.81         | 431                      | 71.0         |
| FS2F           | H795KT/<br>VPSP(7:3)             | 3 hrs at 177°C            | 37.13         | 405                      | 74.9         |
| "              | "                                | +5 hrs post cure at 200°C | 37.11         | 412                      | 74.9         |
| "              | "                                | +5 hrs post cure at 250°C | 36.40         | 410                      | 74.9         |
| "              | "                                | +5 hrs post cure at 300°C | 44.2          | 415                      | 75.1         |
| FS2H           | H795KT/<br>VPSP/DCp<br>(7:3:.5%) | 3 hrs at 177°C            | 41.91         | 393                      | 70.9         |
| "              | "                                | +5 hrs post cure at 200°C | 45.41         | 397                      | 65.7         |
| "              | "                                | +5 hrs post cure at 250°C | 40.1          | 382                      | 71.5         |
| "              | "                                | +5 hrs post cure at 300°C | 45.71         | 416.5                    | 76.3         |
| FS4F           | MY720/<br>DDS                    | 3 hrs at 177°C            | 30.17         | 322                      | 64.0         |

\*DCp: Dicumyl peroxide

## 6. PREPARATION OF DELIVERABLES

Reports and preparation of selected resin and composite panel to be delivered to NASA was completed. The synthetic specification for vinyl-modified styrylpyridine monomer (5-vinyl-2-stilbazole) was delivered in April 1983. The synthetic specification for vinyl/divinyl modified styrylpyridine oligomers was delivered in July 1983. The characterization of the selected matrix resins was delivered in October 1983. One pound of the selected matrix resin solution, which consisted 30 parts of VPSP, 70 parts of H795 KT148 and 100 parts of tetrahydrofuran, was delivered in November 1983. A 6' x 6' nine ply composite panel made from the selected resin (VPSP/H795 = 3/7) was delivered at the end of this phase of the contract.

## 7. CONCLUSIONS AND RECOMMENDATIONS

In the phase I study, HC Chem Research has demonstrated that VST/VPSP can be prepared by a simple synthesis procedure to give a low melt soluble material. VST/VPSP modified bismaleimides are low-temperature curing resins which: reduce water absorption, may be used without solvent or with low boiling solvents, give char yields consistent with optimum fire resistance, have long pot life, and service temperatures of 300°C or above. It is believed that the VPSP-modified bismaleimides described here represent a significant advance in matrix resins for graphite secondary structures where ease of processing, firewothtness, and high-temperature stability are required. VPSP-modified bismaleimide resin composed of 3 parts of VPSP and 7 parts of H795 gave a matrix resin which can be used as light weight graphite fiber reinforced face sheet for aircraft interior panel.


It is recommended that a follow-on effort be initiated with the following objectives:

- (1) Increase the vinyl content of VPSP.
- (2) Examine the long term stability of VST and VPSP at room temperature.
- (3) Examine the mechanism of copolymerization of VST/VPSP and bismaleimide resin by using model compounds.
- (4) Prepare and evaluate light weight aircraft interior panel using VPSP/H795 face sheet and suitable high temperature bond ply.
- (5) Develop a tougher bismaleimide resin system.
- (6) Develop a resin matrix system which can be processed by filament winding method.

## 8. REFERENCES

- (1) H. D. Stenzenberger, Appl. Polym. Symp., 31, 91 (1977).
- (2) I. K. Varma, G. M. Fohlen, and J. A. Parker, J. Polym. Sci. Polym. Chem. Ed., 20, 283 (1982).
- (3) H. D. Stenzenberger, M. Herzog, W. Romer, and R. Scheiblich, Technochemie GmbH-Verfahrenstechnik, Report No. 7908, Project No. NASW 3027, 1979.
- (4) B. Malassin, Proceedings of the 24th National SAMPE Symposium, 24, 1 (1979).
- (5) M. S. Hsu, M. L. Rosenberg, J. A. Parker, and A. H. Heimbuch, J. Appl. Polym. Sci., 26, 1975 (1981).
- (6) J. J. Ratto and C. L. Hamermesh, US Patent 4,362,860 (1982).
- (7) J. D. Seader and W. p. Chien, J. Fire & Flammability 5, 15 (1974)

FIG. 1 VINYL STILBAZOLE (VST) SYNTHESIS



ORIGINAL PAGE  
OF POOR QUALITY

-33-





FIG.2 VST AND VPSP WORK-UP AND SEPARATION

ORIGINAL  
OF POOR QUALITY

FIG. 3 IR SPECTRUM OF VST



ORIGINAL PAGE IS  
OF POOR QUALITY

FIG. 4 NMR OF 5 VINYL-2-STIL BAZOLE (VST)






FIG. 5 TOTAL ION INTENSITY OF VST AT DIFFERENT TEMPERATURE AND TIME  
(DIP RUN)







FIG. 6 MASS SPECTRUM OF VST






ORIGINAL PAGE IS  
OF POOR QUALITY

FIG. 8 NMR SPECTRUM OF PURE VST




ORIGINAL PRINTING  
OF POOR QUALITY

FIG. 9 VINYL STYRYLPYRIDINE (VPSP) SYNTHESIS




ORIGINAL PAGE IS  
OF POOR QUALITY

FIG. 10 IR SPECTRUM OF VPSP




ORIGINAL PAGE IS  
OF POOR QUALITY

FIG.11 NMR OF VINYL POLYSTYRYL PYRIDINE (VPSP)



ORIGINAL PAGE IS  
OF POOR QUALITY


FIG. 12 SIZE EXCLUSION CHROMATOGRAM OF VPSP



\*Molecular weight was corrected by a factor of 1.5 from polystyrene standard  
 $M_n = 950$  (corrected)  
 $M_w = 3500$  (corrected)  
 $M_n = 633$  (uncorrected)  
 $M_w = 2333$  (uncorrected)



Fig. 13 DSC OF BISMALEIMIDE (H795), VST  
AND VST/H795 BLENDS



H795 is H795 M1268





FIG. 14 DSC OF H795 KT148 AND VST/H795 KT148 BLENDS

ORIGINAL PAGE IS  
OF POOR QUALITY

Fig. 15 DSC OF VPSP AND VPSP/H795 BLENDS



H795 is H795 M1268




FIG. 17 · THERMOGRAVIMETRIC ANALYSIS OF VINYLSTYRYLPYRIDINE MODIFIED BISMALEIMIDE IN NITROGEN  
10°C /min






FIG. 18 TYPICAL THERMOGRAVIMETRIC ANALYSIS OF VINYLSTYRYLPYRIDINE MODIFIED BISMALIMIDE IN AIR ( $10^{\circ}\text{C}/\text{min}$ )



ORIGINAL PAGE IS  
OF POOR QUALITY

Fig. 19 ISOTHERMAL DMA OF MODIFIED AND UNMODIFIED  
BISMALEIMIDE PREPREG



H795 is H795 M1268

ORIGINAL  
OF FOUR

FIG. 20 ISOTHERMAL DMA CURVES OF ONE PLY CARBON FIBER PREPREG  
(VPSP/H795 M1268 = 3/7)







FIG. 21 ISOTHERMAL DMA CURVES OF ONE PLY CARBON FIBER  
PREPREG (H795 KT148)








FIG. 23 ISOTHERMAL DMA CURVES OF ONE PLY CARBON FIBER PREPREG  
(VPSP/H795 KT148=3/7)





ORIGINAL CONTENT  
OF POOR QUALITY


**Fig. 24 DMA OF VARIOUS COMPOSITES**




H795 is H795 M1268























FIG. 32 PERCENT WEIGHT LOSS AT 2.5 & 5.0 w/cm<sup>2</sup>  
MY 720-DDS/A193P, Resin Content 17.94%  
Cured at 177°C for 2 hr

Original  
OF PO 11-1-61

DSMS

